BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

NAME OF WORK: Repairs to Anganavadi Building in ward no.8 Kodigehalli.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	7.46	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.50m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications	cum	156.88	Rupees One Hundred Fifty Six and Eighty Eight Paise Only
2	0.75	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement 220kgs,with 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregates @o.465 cum machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation including cost all materials, labour, HOM of machinery, curing complete as per specifications.	cum	5139.94	Rupees Five Thousand One Hundred Thirty Nine and Ninety Four Paise Only
3	3.91	Providing and constructing burnt brick masonry for basement and superstructure with approved quality of non modular bricks of standard size of class designation 3.5 Newton per sqmm with cement 1:6 including cost of materials labour charges scaffolding, curing complete as per specifications.	cum	6095.00	Rupees Six Thousand Ninety Five Only
4	4.00	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes thickness above 200 mm including cost of all materials, labour complete as per specifications.	sqm	396.44	Rupees Three Hundred Ninety Six and Forty Four Paise Only
5	1.00	sump tank cover 24"x24" @ 21kg	Each	1273.00	Rupees One Thousand Two Hundred Seventy Three Only
6	31.21	Dismantling cement concrete flooring or plain cement concrete work including removing and conveying the debries to distance upto 200m (within average thickness of 15cms)	Sqm mtr.	54.06	Rupees Fifty Four and Six Paise Only
7	31.21	Providing and fixing Vetrified glazed tiles of approved make, quality & colour of size 600X600X10mm thick fixed on bed of 12mm thick cement mortar for flooring, skirting and jointed with neat cement slurry mixed with pigment to mach shade tiles, including providing spacers at required interval and removing stains etc., complete as per specifications.	sqm	1134.20	Rupees One Thousand One Hundred Thirty Four and Twenty Paise Only
8	43.79	Providing skirting, dadoing, rises of steps with white glazed tiles 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over existing rough plaster surface using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications.	sqm	940.22	Rupees Nine Hundred Forty and Twenty Two Paise Only

No & corrections - None

15/12

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬ್ರ.ಬೆ.ಮ.ಪಾ., ಬೆಂಗಳೂರು

15/12

	Quantity.	Description	Unit	Rates	
				In Figures	In Words
9	9.48	Providing and laying platform using prepolished watre cut / gang saw 40mm thick telephonic Black granite. Laid on existing vertical supports and fixing in CM 1:3 proportion. Including cutting to required shape, pattern with paper joints including full rounding for nosing finished with cement mortar, pointed with colour pigments to match the colour of slab making through jointing with sealant, making holes 25mm X 12mm grooves in joints including curing	sqm	3768.30	Rupees Three Thousand Seven Hundred Sixty Eight and Thirty Paise Only
10	1.00	Providing and fixing kitchen sink of white glazed fire clay of size 600x450x250mm with M.S /C.I brackets, C.P brass chain with rubber plug, 32 mm C.P brass waste, tap with union, brass stop cock complete, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications.	Unit	3666.54	Rupees Three Thousand Six Hundred Sixty Six and Fifty Four Paise Only
11	1.00	Providing and fixing white vitreous chaina clay, flat back Wash basin size 550x400mm with a pair of 15mm C.P brass pillar taps painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications.	Unit	3770.42	Rupees Three Thousand Seven Hundred Seventy and Forty Two Paise Only
12	1.00	Providing and fixing white vitreous china clay, water closet Indian type (Squating pan) of size 580 mm with footrests, 100mm S or P trap, 10 litre low level, P.V.C flushing cistern (all are approved make) with fittings, C.I / M.S brackets, 32mm diameter flush pipe fittings and clamps, overflow arrangements with special and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications.	No	3620.96	Rupees Three Thousand Six Hundred Twenty and Ninety Six Paise Only
13	162.36	Removing white wash or colour wash by steel brushing and/or scraping, sand papering and preparing wall surface smooth including repairs to scraches, cost of complete as per specifications.	sqm	5.83	Rupees Five and Eighty Three Paise Only
14	39.60	Extra for removing white wash or colour wash by steel brushing and/or scraping, sand papering the ceiling and /or sloping roof surface smooth including repairs to scraches, cost of labour, complete as per specifications.	sqm	6.36	Rupees Six and Thirty Six Paise Only
15	43.79	Dismantling plastering and removing the debries with a lead upto 200m	sqm	23.32	Rupees Twenty Three and Thirty Two Paise Only
~~16~~ 17	71.63	Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after throughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications.	sqm	69.96	Rupees Sixty Nine and Ninety Six Paise Only
~~17~~ 18	39.60	Extra over item 15-14. 1 for applying oil bound washable distemper on ceiling and / or sloping roof as per specifications.	sqm	4.77	Rupees Four and Seventy Seven Paise Only
~~18~~ 19	72.93	Providing Gopi colour washing to new wall surface in two coats with lime and gopi colour of approved quality, to give an even shade after throughly brooming the surface to remove all dirt, dust, mortar drops and other foreign matter including cost of materials, labour complete as per specifications.	sqm	10.60 ~~10.80~~	Rupees Ten and ~~Eighty~~ Sixty Paise Only

(16) Dismantling plastering and removing the debries with a lead upto 200m. (I.No 37.50 PWD 2015-16)
No of corrections - Nil

15/12
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬ.ಬೆ.ಮ.ಪಾ., ಬೆಂಗಳೂರು

15/12

	Quantity.	Description	Unit	Rates	
				In Figures	In Words
19	20.74	Providing and applying enamel metal paint two coats (excluding priming coat)over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications	sqm	83.74	Rupees Eighty Three and Seventy Four Paise Only
20	52.92	Providing applying water proofing to roof slab, terraces, landcape area, podium etc., using modified polyurethane cures (confirming to ASTM C836 - 84) to give a tough elastomeric waterproof membrane on the surface. The surface shall be cleaned free from dust and other particle before usage	sqm	742.00	Rupees Seven Hundred Forty Two Only
21	7.46	Lead for disposal of debris shall be payable at carrage rates by mechanical means including loading and unloading From 13.30 Kms	cum	114.08	Rupees One Hundred Fourteen and Eight Paise Only

No & corrections - Nil

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore -92

15/12

Note:

1. Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
2. Unit rates and prices shall be quoted by the Tender in Indian rupees.
3. Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4. Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

ಕರಡು ಟೆಂಡರ್ ಪಡ್ಯೂಲ್‌ನ್ನು
ಶಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ.....(
ಶಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದ್ದನೆ ನೀಡಿರಾಗಿದೆ